ASSEMBLY INSTRUCTIONS



OZtrail advises to assemble your Shelter before use to ensure all parts are present and to become familiar with the assembly of your shelter. Chose a flat level area with no objects that could damage the floor. Layout out the shelter facing the desired direction. Peg out the four corners of the shelter floor. Anchor the shelter to the ground by inserting the pegs through the ring loops at each corner of the floor at an angle of 45 degrees. Firm but not tight. As you work from one peg point to the other around the shelter base pull the floor firmly, but not tight. If on sand fill the sand bags to anchor the shelter in position.

Helpful Hint: Be careful not to twist or force the frame assembly when unfolding the shelter. Until you are locking the central roof hub into its final position, it is not necessary at any stage of shelter assembly to apply more than a small force on the frame. If a small force is not sufficient to carry out each described step, then realign the frame and try again.

Step 1: Lay shelter flat with central hub upright. Make sure poles are fully extended and spread out.

Step 2: Grip lower hub of shetler and lift to eye level. With the other hand, begin to pull cord.

Step 3: Continue to pull cord back like drawing a bow. As the hub gets closer to connecting, the resistance will increase and the shelter will bow out.

Ensure all peg down points are utilised and remain firm. Ensure the shelter remains securely anchored at all times.

In severe conditions the shelter should be dismantled.

To pack away, simply pull down on the lower portion of the central frame hub to release tension and then reverse the above.







STEP 1. STEP 2. STEP 3.